



---

## Idaho Department of Environmental Quality Draft §401 Water Quality Certification

October 21, 2016

**404 Permit Application Number:** NWW-2014-186-C09; Burke Bank Stabilization

**Applicant/Authorized Agent:** Robert Burke 3602 Sherwood Drive Coeur d'Alene, ID 82815

**Project Location:** 49N R2E section 3; Latitude 47°37'32.08"N Longitude 116°11'48.41"W

**Receiving Water Body:** North Fork Coeur d'Alene River

---

Pursuant to the provisions of Section 401(a)(1) of the Federal Water Pollution Control Act (Clean Water Act), as amended; 33 U.S.C. Section 1341(a)(1); and Idaho Code §§ 39-101 et seq. and 39-3601 et seq., the Idaho Department of Environmental Quality (DEQ) has authority to review activities receiving Section 404 dredge and fill permits and issue water quality certification decisions.

Based upon our review of the revised joint application for permit, received on October 6, 2016, DEQ certifies that if the permittee complies with the terms and conditions imposed by the permit along with the conditions set forth in this water quality certification, then there is reasonable assurance the activity will comply with the applicable requirements of Sections 301, 302, 303, 306, and 307 of the Clean Water Act, the Idaho Water Quality Standards (WQS) (IDAPA 58.01.02), and other appropriate water quality requirements of state law.

This certification does not constitute authorization of the permitted activities by any other state or federal agency or private person or entity. This certification does not excuse the permit holder from the obligation to obtain any other necessary approvals, authorizations, or permits.

### Project Description

The applicant proposes to stabilize 1,620 feet of North Fork Coeur d'Alene River bank using a total of 2,160 cubic yards of 30 inch minus angular rock riprap of which 1,730 cubic yards will be located below the ordinary high water mark. The project also proposes to install 25 root wads and rock clusters, and 324 willow bundles. A toe trench will be created by pushing the riverbed gravels outward before excavating the toe trench. This technique creates its own cofferdam around the toe trench and the riverbed gravels are suitable materials at this location for the success of this technique during low pool when only a small amount of disturbance will occur in the flowing water. Excavated riverbed for the toe trench will be used to fill voids in the banks. Root wads and rock clusters will be placed to improve aquatic habitat and willows will add shade to locations currently void of riparian vegetation and will be used to restore riparian areas cleared for access to complete this project. This is an NRCS designed project and they will provide oversight during construction.

## Antidegradation Review

The WQS contain an antidegradation policy providing three levels of protection to water bodies in Idaho (IDAPA 58.01.02.051).

- Tier 1 Protection. The first level of protection applies to all water bodies subject to Clean Water Act jurisdiction and ensures that existing uses of a water body and the level of water quality necessary to protect those existing uses will be maintained and protected (IDAPA 58.01.02.051.01; 58.01.02.052.01). Additionally, a Tier 1 review is performed for all new or reissued permits or licenses (IDAPA 58.01.02.052.07).
- Tier 2 Protection. The second level of protection applies to those water bodies considered high quality and ensures that no lowering of water quality will be allowed unless deemed necessary to accommodate important economic or social development (IDAPA 58.01.02.051.02; 58.01.02.052.08).
- Tier 3 Protection. The third level of protection applies to water bodies that have been designated outstanding resource waters and requires that activities not cause a lowering of water quality (IDAPA 58.01.02.051.03; 58.01.02.052.09).

DEQ is employing a water body by water body approach to implementing Idaho's antidegradation policy. This approach means that any water body fully supporting its beneficial uses will be considered high quality (IDAPA 58.01.02.052.05.a). Any water body not fully supporting its beneficial uses will be provided Tier 1 protection for that use, unless specific circumstances warranting Tier 2 protection are met (IDAPA 58.01.02.052.05.c). The most recent federally approved Integrated Report and supporting data are used to determine support status and the tier of protection (IDAPA 58.01.02.052.05).

### ***Pollutants of Concern***

The primary pollutant of concern for this project is sediment and temperature. As part of the Section 401 water quality certification, DEQ is requiring the applicant comply with various conditions to protect water quality and to meet Idaho WQS, including the water quality criteria applicable to sediment and temperature.

### ***Receiving Water Body Level of Protection***

This project is located on North Fork Coeur d'Alene River within the Upper Coeur d'Alene Subbasin assessment unit (AU) ID17010301PN001\_05 (North Fork Coeur d'Alene River below Prichard Creek). This AU has the following designated beneficial uses: cold water aquatic life, salmonid spawning, primary contact recreation and domestic water supply. In addition to these uses, all waters of the state are protected for agricultural and industrial water supply, wildlife habitat, and aesthetics (IDAPA 58.01.02.100).

According to DEQ's 2012 Integrated Report, this AU is not fully supporting its cold water aquatic life use and salmonid spawning uses. Causes of impairment include other flow regime alterations, physical substrate habitat alterations, sedimentation/siltation and temperature. The contact recreation beneficial use is fully supported. As such, DEQ will provide Tier 1 protection

(IDAPA 58.01.02.051.01) for the aquatic life use and Tier 2 protection (IDAPA 58.01.02.051.02) in addition to Tier 1 for the contact recreation use (IDAPA 58.01.02.052.05.c).

The only pollutants of concern associated with this project are sediment and temperature, but sediment and temperature are not relevant to recreational uses; therefore, it is unnecessary for DEQ to conduct a Tier 2 review for this AU because this project will not create impacts that could affect the recreation use.

### ***Protection and Maintenance of Existing Uses (Tier 1 Protection)***

As noted above, a Tier 1 review is performed for all new or reissued permits or licenses, applies to all waters subject to the jurisdiction of the Clean Water Act, and requires demonstration that existing uses and the level of water quality necessary to protect existing uses shall be maintained and protected. The numeric and narrative criteria in the WQS are set at levels that ensure protection of designated beneficial uses.

Water bodies not supporting existing or designated beneficial uses must be identified as water quality limited, and a total maximum daily load (TMDL) must be prepared for those pollutants causing impairment. Once a TMDL is developed, discharges of causative pollutants shall be consistent with the allocations in the TMDL (IDAPA 58.01.02.055.05). Prior to the development of the TMDL, the WQS require the application of the antidegradation policy and implementation provisions to maintain and protect uses (IDAPA 58.01.02.055.04).

During the construction phase, the applicant will implement, install, maintain, monitor, and adaptively manage best management practices (BMPs) directed toward reducing erosion and minimizing turbidity levels in receiving water bodies downstream of the project. In addition, permanent erosion and sediment controls will be implemented, which will minimize or prevent future sediment contributions from the project area. This project will be implemented during low pool to reduce the potential for turbidity. As long as the project is conducted in accordance with the provisions of the revised project plans, Section 404 permit, and conditions of this certification, then there is reasonable assurance the project will comply with the state's numeric and narrative criteria. These criteria are set at levels that protect and maintain designated and existing beneficial uses. In addition, the project will be consistent with the *Subbasin Assessment and Total Maximum Daily Loads of the North Fork Coeur d'Alene River* (DEQ 2001) and the *Upper (North Fork) Coeur d'Alene River Subbasin Temperature Total Maximum Daily Loads*, (DEQ 2013). The sediment TMDL requires a load reduction of sediment in this watershed and the temperature TMDL requires additional shade. This project proposes to stabilize banks that are actively eroding, some up to six feet in height. The project will also place willow bundles along the entire length of the project, some of which is currently void of all riparian vegetation. Access points will be planned so as to minimize cutting of riparian vegetation in areas where it exists. There will be a net increase of shade if willow plantings are successful.

There is no available information indicating the presence of any existing beneficial uses aside from those that are already designated and discussed above; therefore, the permit ensures that the level of water quality necessary to protect both designated and existing uses is maintained and protected in compliance with the Tier 1 provisions of Idaho's WQS (IDAPA 58.01.02.051.01 and 58.01.02.052.07).

## Conditions Necessary to Ensure Compliance with Water Quality Standards or Other Appropriate Water Quality Requirements of State Law

### ***General Conditions***

1. This certification is conditioned upon the requirement that any modification (e.g., change in BMPs, work windows, etc.) of the permitted activity shall first be provided to DEQ for review to determine compliance with Idaho WQS and to provide additional certification pursuant to Section 401. Such modifications may not be implemented until DEQ has determined whether additional certification is necessary.
2. DEQ reserves the right to modify, amend, or revoke this certification if DEQ determines that, due to changes in relevant circumstances—including without limitation, changes in project activities, the characteristics of the receiving water bodies, or state WQS—there is no longer reasonable assurance of compliance with WQS or other appropriate requirements of state law.
3. If ownership of the project changes, the certification holder shall notify DEQ, in writing, upon transferring this ownership or responsibility for compliance with these conditions to another person or party. The new owner/operator shall request, in writing, the transfer of this water quality certification to his/her name.
4. A copy of this certification must be kept on the job site and readily available for review by any contractor working on the project and any federal, state, or local government personnel.
5. Project areas shall be clearly identified in the field prior to initiating land-disturbing activities to ensure avoidance of impacts to waters of the state beyond project footprints.
6. The applicant shall provide access to the project site and all mitigation sites upon request by DEQ personnel for site inspections, monitoring, and/or to ensure that conditions of this certification are being met.
7. The applicant is responsible for all work done by contractors and must ensure the contractors are informed of and follow all the conditions described in this certification and the Section 404 permit.

### ***Fill Material***

8. Fill material shall be free of organic and easily suspended fine material. The fill material to be placed shall include clean stone only.
9. Fill material shall not be placed in a location or in a manner that impairs surface or subsurface water flow into or out of any wetland area.
10. All temporary fills shall be removed in their entirety on or before construction completion.
11. Excavated or staged fill material must be placed so it is isolated from the water edge or wetlands and not placed where it could re-enter waters of the state.

## **Erosion and Sediment Control**

12. BMPs for sediment and erosion control suitable to prevent exceedances of state WQS shall be selected and installed before starting construction at the site. One resource that may be used in evaluating appropriate BMPs is DEQ's *Catalog of Stormwater Best Management Practices for Idaho Cities and Counties*, available online at <http://www.deq.idaho.gov/media/494058-entire.pdf>. Other resources may also be used for selecting appropriate BMPs.
13. One of the first construction activities shall be placing permanent and/or temporary erosion and sediment control measures around the perimeter of the project or initial work areas to protect the project water resources.
14. Permanent erosion and sediment control measures shall be installed in a manner that will provide long-term sediment and erosion control to prevent excess sediment from entering waters of the state.
15. Erosion and sediment control measures shall be installed at the earliest practicable time consistent with good construction practices and shall be maintained as necessary throughout project operation.
16. At a minimum, BMPs must be inspected and maintained daily during project implementation. BMPs shall be replaced or augmented if they are not effective.
17. All construction debris shall be properly disposed of so it cannot enter waters of the state or cause water quality degradation.
18. Disturbed areas suitable for vegetation shall be seeded or revegetated to prevent subsequent soil erosion.
19. Sediment from disturbed areas or able to be tracked by vehicles onto pavement must not be allowed to leave the site in amounts that would reasonably be expected to enter waters of the state. Placement of clean aggregate at all construction entrances or exits and other BMPs such as truck or wheel washes, if needed, must be used when earth-moving equipment will be leaving the site and traveling on paved surfaces.

## **Turbidity**

20. Sediment resulting from this activity must be mitigated to prevent violations of the turbidity standard as stipulated under the Idaho WQS (IDAPA 58.01.02). *Any violation of this standard must be reported to the DEQ regional office immediately.*
21. All practical BMPs on disturbed banks and within the waters of the state must be implemented to minimize turbidity. Visual observation is acceptable to determine whether BMPs are functioning properly. If a plume is observed, the project may be causing an exceedance of WQS and the permittee must inspect the condition of the projects BMPs. If the BMPs appear to be functioning to their fullest capability, then the permittee must modify the activity or implement additional BMPs (this may also include modification of existing BMPs).

***In-water Work***

22. Work in open water is to be kept at a minimum and only when necessary. Equipment shall work from an upland site to minimize disturbance of waters of the state.
23. Construction affecting the bed or banks shall take place only during periods of low flow.
24. Fording of the channel is not permitted.
25. Heavy equipment working in wetlands shall be placed on mats or suitably designed pads to prevent damage to the wetlands.
26. Activities in spawning areas must be avoided to the maximum extent practicable.
27. Work in waters of the state shall be restricted to areas specified in the application.

***Vegetation Protection and Restoration***

28. To the maximum extent practical, staging areas and access points should be placed in open, upland areas.
29. Fencing and other barriers should be used to mark the construction areas.
30. If authorized work results in unavoidable vegetative disturbance, riparian and wetland vegetation shall be successfully reestablished to function for water quality benefit at pre-project levels or improved at the completion of authorized work.

***Management of Hazardous or Deleterious Materials***

31. Petroleum products and hazardous, toxic, and/or deleterious materials shall not be stored, disposed of, or accumulated adjacent to or in the immediate vicinity of waters of the state. Adequate measures and controls must be in place to ensure that those materials will not enter waters of the state as a result of high water, precipitation runoff, wind, storage facility failure, accidents in operation, or unauthorized third-party activities.
32. Vegetable-based hydraulic fluid should be used on equipment operating in or directly adjacent to the channel if this fluid is available.
33. Daily inspections of all fluid systems on equipment to be used in or near waters of the state shall be done to ensure no leaks or potential leaks exist prior to equipment use. A log book of these inspections shall be kept on site and provided to DEQ upon request.
34. Equipment and machinery must be removed from the vicinity of the waters of the state prior to refueling, repair, and/or maintenance.
35. Equipment and machinery shall be steam cleaned of oils and grease in an upland location or staging area with appropriate wastewater controls and treatment prior to entering a water of the state. Cleaning should be sufficient enough to remove any invasive species including plant, animal or larval stages. Any wastewater or wash water must not be allowed to enter a water of the state.
36. Emergency spill procedures shall be in place and may include a spill response kit (e.g., oil absorbent booms or other equipment).
37. In accordance with IDAPA 58.01.02.850, in the event of an unauthorized release of hazardous material to state waters or to land such that there is a likelihood that it will enter state waters, the responsible persons in charge must

- a. Make every reasonable effort to abate and stop a continuing spill.
  - b. Make every reasonable effort to contain spilled material in such a manner that it will not reach surface or ground waters of the state.
  - c. Immediately notify DEQ of the spill by calling the Idaho State Communications Center at 1-800-632-8000.
  - d. Collect, remove, and dispose of the spilled material in a manner approved by DEQ.
38. Any release that causes a sheen (of any size) in waters of the state must be reported *immediately* to the National Response Center at 1-800-424-8802 and DEQ by calling the Idaho State Communications Center at 1-800-632-8000.

## Right to Appeal Final Certification

The final Section 401 Water Quality Certification may be appealed by submitting a petition to initiate a contested case, pursuant to Idaho Code § 39-107(5) and the “Rules of Administrative Procedure before the Board of Environmental Quality” (IDAPA 58.01.23), within 35 days of the date of the final certification.

Questions or comments regarding the actions taken in this certification should be directed to June Bergquist at (208) 666-4605 or [june.bergquist@deq.idaho.gov](mailto:june.bergquist@deq.idaho.gov).

DRAFT

---

Daniel Redline  
Regional Administrator  
Coeur d'Alene Regional Office